

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22401-00-00
Spot: NWNENW Sec/Twnshp/Rge: 15-31S-3E
4713 feet from S Section Line, 3347 feet from E Section Line
Lease Name: HANN B Well #: 4
County: COWLEY Total Vertical Depth: 3134 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3134		140 SX CMT
SURF	8.625	205		85 SX CMT

\$ 101.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2006 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: BRENT WHITEMAN Company: GEN-DOR OIL COMPANY Phone: (620) 222-1808

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/14/2006 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

6/9/2006 -- Sanded back 66' above perforations at 3010'; dump bailed 6 sacks of cement on top. Shot 5-1/2" casing at 1568'. POOH with 39 joints of 5-1/2" casing.
6/14/2006 -- RIH with tubing at 360'. Gen-Dor mixed and pumped 161 sacks of 60/40 posmix with 4% gel to surface.
United Cementing #6700

Perfs:

Top	Bot	Thru	Comments
3076	3084		

**RECEIVED
KCC DISTRICT #2
JUL - 5 2006
WICHITA, KS**

INVOICED

DATE 7-27-06
NO. 2007060281

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

**RECEIVED
JUL 26 2006
KCC WICHITA**

m

PT