

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20039-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 32-16S-19W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: OHNMACHT Well #: 4
County: RUSH Total Vertical Depth: 3820 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1313		WITH 425 SX CMT
PKR		3776		
PROD	4.5	3809	0	WITH 100 SX CMT
SURF	8.625	256		

\$ 124.15

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2006 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: PUMP 25 SX CMT WITH 100# HULLS. PLUG AT 1200' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2006 12:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


SQUEEZED FROM 490' TO 2200'. LOCKSET PACKER IN HOLE AT 3776'. RAN TUBING TO 3668' & PUMPED 25 SX CMT WITH 100# HULLS. PULLED TUBING TO 1215'. CIRCULATED CMT TO SURFACE UP 4 1/2" CASING WITH 75 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF 4 1/2" WITH 15 SX CMT. MAXIMUM PRESSURE 500 PSIG. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS WITH 30 SX CMT. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 200 PSIG.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.
Plugged through: TBG

INVOICED
DATE 7-28-06
TR. NO. 2007060280

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
JUL 27 2006
KCC WICHITA

Form CP-23
[Signature]
PKF