

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23201-00-00
Spot: NESWNW Sec/Twnshp/Rge: 21-6S-21W
1750 feet from N Section Line, 1120 feet from W Section Line
Lease Name: VOSS Well #: 1-21
County: GRAHAM Total Vertical Depth: 3860 feet

Operator License No.: 32686
Op Name: REILLY OIL COMPANY, INC.
Address: 3501 YALE ROAD
LAWRENCE, KS 66049

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	209		

\$ 125.45

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/25/2006 11:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: DUSTY RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Arbuckle penetrated but very tite.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 07/25/2006 12:01 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 1950' w/25 sxs.
2nd Plug at 1150' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

INVOICED
7-28-06
2007060289

JUL 26 2006

RECEIVED
JUL 27 2006
KCC WICHITA

Form CP-2/3

ART