

RECEIVED

JUL 24 2006

KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15- 135-21,133-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_

Well Operator: VESS OIL CORPORATION KCC License #: 5030

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita

State: KS Zip Code: 67226 Contact Phone: ( 316 ) 682 - 1537 X103

Lease: Putnam B Well #: 3 Sec. 36 Twp. 20S S. R. 26W ☐ East ☒ West

NE SW Spot Location / QQQQ County: Ness

1980' Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

3300' 1980' Feet (in exact footage) From East / ☒ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☒ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well

☐ SWD Docket # \_\_\_\_\_ ☐ ENHR Docket # \_\_\_\_\_ ☐ Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 299' Cemented with: 225 Sacks

Production Casing Size: 4-1/2" Set at: 4411' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Miss OH 4411-19'; casing leak repairs: 1267-98': 20 sx; 2946-97': 20 sx;

3177-90': 200 sx, 200 sx, 3662-94': 200 sx

Elevation: 2433/2438 (☒ G.L. / ☒ K.B.) T.D.: 4419' PBTD: 4419' Anhydrite Depth: 1645-1686; 1049-1061 Blaine

Condition of Well: ☐ Good ☐ Poor ☒ Casing Leak ☐ Junk in Hole parted casing: 2035-2068

Proposed Method of Plugging (attach a separate page if additional space is needed): Run tbg to 2025'; spot 40 sx Class A, 3% cc, plug. Pull up, wireline tag plug.

Spot 2nd plug at 1200': 25 sx Class A, 3%cc. Wireline tag it, load casing and test to 200#. Perf circ. holes @ 1100'. Pump to get circ.: cement with 160 sx 60/40 pozmix, 6% gel, try to circ. up backside to surface. Have 150 sx extra if no circ. to pump down backside

Is Well Log attached to this application as required? ☒ Yes ☐ No Is ACO-1 filed? ☒ Yes ☐ No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ken Rupp

Phone: ( 785 ) 798 - 5260 - cell

Address: 218-1/2 N. High Street City / State: Ness City, KS 67560

Plugging Contractor: North Fork Well Service, LLC KCC License #: 32938

Address: 7 SW 26th Ave, Great Bend, KS 67530 Phone: ( 620 ) 793 - 3051

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/21/06 Authorized Operator / Agent: Barry Boate (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Kcc  
Wichita  
OGR  
7-22



# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   Robert E. Krehbiel, Commissioner   Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Vess Oil Corporation  
8100 E. 22nd N. Bldg. 300  
Wichita, KS 67226

July 25, 2006

Re: PUTNAM B #3  
API 15-135-21133-00-00  
NESW 36-20S-26W, 1980 FSL 1980 FWL  
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888