



15-141-20015-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1972

CONSERVATION DIVISION
Wichita, Kansas

8-18-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ehrlich of E & G Exploration has this

date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: E & G Exploration

Complete Address: Box 338 Wilson, Kansas

Lease Name: Becker Well No. 1

Location: C NE SW NE Sec. 15 Twp. 8 Rge. (E)(W) 11

County: Osborne Total Depth 2985' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 480' and displace

50 sk cmt thru drill pipe. Heavy mud to 150' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Warrick
Conservation Division Agent