



15-141-20084-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of Pioneer Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 400 N. Woodlawn, Suite 201, Wichita, Ks.

Lease Name: Roadhouse Well No. 2

Location: SW NW NW Sec. 19 Twp. 8 Rge. (E)(W) 13

County: Osborne Total Depth 2755' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill

pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1978

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas
11-27-78

Conservation Division Agent