



15-163-20455-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1972

CONSERVATION DIVISION
Wichita, Kansas

8-17-72

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Vickers KSB&T Bldg., Wichita, Ks.

Lease Name: Taylor Well No. 1

Location: NW NW NW Sec. 1 Twp. 8 Rge. (E)(W) 17

County: Rooks Total Depth 3225' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Fickle was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 550' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo Z. Messer
Conservation Division Agent