



15-163-20521-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1974

CONSERVATION DIVISION  
Wichita, Kansas

5-24-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Buchheister of Farmer Drlg. has this

date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer

Complete Address: Box 352 370 W. Wichita Ave., Russell, Ks.

Lease Name: Behrens Well No. 1

Location: SE SW NE Sec. 2 Twp. 8 Rge. (E)(W) 17

County: Rooks Total Depth 3315' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Buchheister was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 550' and displace  
70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Murray  
Conservation Division Agent