

3 022996

15-207-01622-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

CONTROL NO. 20050048-020

SE

NE,SW,SE 1/4

Sec/Twp/Rge S.34-T.26S.-R.16E.

711 feet from south section line

1372 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 100701

Lease/Well#

JOHNSON NO.6-I

Operator: STATE OF KANSAS

County

WOODSON

Name & FEE FUND PLUGGING

Well Total Depth

1000' feet

Address

Production Pipe: 2"

Size Feet 1000'

Surface Casing: 6"

Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING & ROUSTABOUT SERVICE

Lic. #

6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 16 Month: 1 2006

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 12:00p.m. Day: 16 Month: 1 2006

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 6" ANNULUS

TO 300'. AT THAT DEPTH SOLID CEMENT WAS ENCOUNTERED. CEMENT WAS PUMPED INTO

THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE

1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 70 SACKS OF

CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.20) (THIS WELL WAS NO.6-I ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED

JAN 23 2006

KCC WICHITA

Signed:

Clayton P. Titel
TECHNICIAN

PPT