

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23018-00-00
Spot: NENESW Sec/Twnshp/Rge: 23-26S-19E
2181 feet from S Section Line, 3229 feet from E Section Line
Lease Name: ROBERTS Well #: 12-R
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0
Op Name: LANDOWNER
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.5	40		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2006 12:30 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION COMPANY Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 04/06/2006 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750PSI. 25 SACKS OF CEMENT WRER PUMPED INTO THIS WELL.

Perfs:

RECEIVED
AUG 02 2006
KCC WICHITA

INVOICED
DATE 8-3-06
INVOICE NO. 2007060311

Remarks: SPOT LOCATINO ESTABLISHED BY GPS SURVEY AS SESSION POINT NO39. (CPT 05/17/06)

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PKT