

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-01050-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 4-16S-11W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: DAVIDSON Well #: 1  
County: BARTON Total Vertical Depth: 3341 feet

Operator License No.: 30081  
Op Name: ANSHUTZ, EVELYN DBA ANSUTZ OIL  
Address: PO BOX 274  
ELLSWORTH, KS 67439

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	18	12		
PROD	4.5	2992	1500	w/125 sxs cmt
SURF	7.5	365	0	

\$ 108.58

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2006 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: LARRY DOLECHEK Company: ANSHUTZ OIL Phone: (785) 658-3528

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/24/2006 3:00 PM KCC Agent: ROGER MOSES

**Actual Plugging Report:**

Sanded back to 2800' w/5 sxs cement.  
Shot 4 1/2" casing off at 1500' - pulled one joint - spotted 75 sxs cement w/300# hulls.  
Pulled casing to 750' - spotted 30 sxs cement with 100# hulls.  
Pulled casing to 450' - spotted 30 sxs cement with 100# hulls.  
Pulled casing to 150' - circulated with 25 sxs cement.  
Pulled all casing and cellar remained full.  
Total 160 sxs 60/40 pozmix - 10% gel and 500# hulls.

**Perfs:**

Top	Bot	Thru	Comments
3165			
2824			

INVOICED

DATE 8-3-06  
TEL NO. 2007060303

RECEIVED  
AUG 02 2006  
KCC WICHITA

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

10

Signed Roger Z Moses  
(TECHNICIAN)

JUL 27 2006

ACT

STATE: KANSAS COUNTY: BARTON OWWO 4-16S-11W  
FIELD: DAVIDSON DAVIDSON FLD (MULTIPAY) SW SW NE  
OPER: O G H OIL 2970 FSL 2310 FEL SEC  
WELL: 1 DAVIDSON WELL CLASS: D ELEV: 1845 GR  
API: 15-009-15158-0001 STATUS: TAW  
SPUD: 10/15/91 COMP: 07/15/92  
DTD: 3341 LTD: FTD: ARBUCKLE PBTD:

LOC: 5 1/2 MI NE HITCSHMANN, KS

IP: COMP 7/15/92, TEMP ABND DELAYED COMPLETION

OWWO: OWWO: OLD INFO: FORMERLY SYNDICATE O & G # 1 POIRANO. SPUD 09/17/30. 6  
@ 3095 W/CMT. SPL TOPS: CONGL 3260, ARBUCKLE 3307, OTD 3341, COMP  
12/17/30. D&A NEW INFO: TO RETEST.

DRLG COMMENTS: OPERATOR IS ATTEMPTING WORKOVER WITH HIS OWN PULLING  
UNIT & TOOLS AND HAS ENCOUNTERED ENORMOUS AMT OF JUNK IN HOLES

OPER ADD: RR 1 BOX 87, WILSON, KS, 67490 PHONE (913) 658-3528;  
CONTR: DOLECHEK LARRY

WAOICED