

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21996-00-00  
Spot: SENENW Sec/Twnshp/Rge: 12-10S-18W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ROSS Well #: 2  
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE ROAD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3400		
CIBP		3640		
DVT		1452		500 SX
PROD	5.5	3787	0	275 SX
SURF	8.625	288	0	170 SX

\$123.50

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2006 10:30 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
DV Tool at 1452' w/500 sxs. CIBP at 3400'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2006 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

07-25-2006 - Fisher Well Service sandline drilled CIBP at 3400'.  
07-26-2006 - Allied pumped 185 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside instant pressure 500#.

Perfs:

Top	Bot	Thru	Comments
3680	3682		
3580	3586		
3554	3560		
3534	3540		
3516	3520		
3509	3513		
3497	3503		
3473	3481		

INVOICED  
DATE 8-3-06  
INVOICE NO. 2007060308  
RECEIVED  
AUG 02 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

H.D. Signed Richard Williams  
(TECHNICIAN)

JUL 28 2006

RET

INDICATED

FRONTIER OIL COMPANY

1720 KSB BUILDING

WICHITA, KS 67202

#2 ROSS

12-10-18W


SE NE NW

CONTR RED TIGER DRILLING CO.

CTY ROOKS

GEOL STEVEN D. ANGLE

FIELD PLAINVILLE



ELV 2117 KB SPD 3/22/83

CARD ISSUED 7/7/83

IP OIL WELL

API 15-163-21,996

LKC 3473-3586 OA

SMP	Tops	Depth/Datum
ANH	1447+	670
BRNVLE	2773-	656
TARK	2876-	759
TOP	3078-	961
HEEB	3296-	1179
TOR	3314-	1197
LKC	3338-	1221
BKC	3591-	1474
SIMP	3663-	1546
ARB	3684-	1567
RTD	3800-	1683

8 5/8 " 288/170SX; 4 1/2 " 3787/775SX; DV TOOL AT 1450

DST (1) 3059-3120 (TOP) / 60-30-60-30, REC 260' MW, SIP 1288-1186#, FP51-104 / 104-145#

DST (2) 3216-3300 (TOP) / 60-30-60-30, REC 185' M, SIP 1278-1237#, FP 103-124 / 134-166#

DST (3) 3290-3407 (SHAW, LKC) / 60-30-60-30, REC 275' WM, SIP 1400-1339#, FP 83-156 / 156-207#

DST (4) 3404-22 (LKC) / 60-30-30-30, REC 5' M, SIP 41-623, FP 27-27 / 27-27#

DST (5) 3460-3520 (LKC) / 60-30-60-30, REC 120' OIL SPKD M, SIP 539-456#, FP 51-83 / 103-124#

DST (6) 3520-84 (LKC) / 60-30-60-30, REC 175' OCM, SIP 1216-971#, FP 72-93 / 93-104#

(over)

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS