

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21685-00-00
Spot: NENESW Sec/Twnshp/Rge: 12-10S-18W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BARDOT Well #: 2
County: ROOKS Total Vertical Depth: 3757 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3755	0	250 SX
SURF	8.625	261	0	165 SX

\$ 122.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2006 8:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV Tool 1473' w/550 sxs cwc. CIBP 3400'. MIT for TA status 300#.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2006 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

07-21-2006 - Fisher Well Service sandline drilled CIPB at 3400' out.
07-24-2006 - Allied pumped 185 sxs 60/40 pozmix - 10% gel with 450# hulls down 4 1/2" casing.
Max. P.S.I. 800#. S.I.P. 400#.
Hooked up to backside and pumped 25 sxs cement with 50# hulls.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3598	3606		
3572	3582		
3536	3540		
3518	3524		
3492	3498		

INVOICED
DATE 8-3-06
2007060308

RECEIVED

AUG 02 2006

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. RGN TANK SERVICE.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

JUL 28 2006

PKT

FRONTIER OIL CO.

1720 KANSAS STATE BANK BLDG.

WICHITA, KS 67202

CONTR RED TIGER DRG. CO.

#2 BARDOT

CTY ROOKS

12-10-18W
NE NE SW

GEOL RICHARD D PARKER

FIELD PLAINVILLE EXT (1/8 N)

E 2144 KB CM 5/17/82 ^{CARD} ISSUED 8/19/82 IP P 18.29 80 & 40.71

API 15-163-21,685

BWPD
LKC 3492-3582 OA
PENN 3598-3606

	+	+	+
	.	.	.
	+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		1475	+ 669
BRNVLE		2793	- 649
TARK		2900	- 756
HOW		3073	- 929
HEEB		3101	- 957
TOR		3342	-1198
LKC		3362	-1218
BKC		3594	-1450
CONG		3613	-1469
CHT CONG		3665	-1521
ARB		3716	-1572
RTD		3757	-1613
NO LOG			

INDEPENDENT OIL & GAS SERV
WICHITA, KANSAS

8-5/8" 260/165sx, 4 1/2" 3755/250sx,
FO TOOL 1473

DST (1) 3429-3451(LKC)/60-30-30-30,
REC 30'M, SIP 1467-1467#, FP
10-20/20-20#

DST (2) 3466-3546(LKC)/60-30-60-30,
REC 80'SOCM, SIP 1220-1138#, FP
62-83/83-104#

DST (3) 3544-3570(LKC)/30-30-30-30,
REC 5'M, NS, SIP 0-0#, FP 0-0/
0-0#

DST (4) 3566-3614(PENN)/60-30-30-30,
REC 10'M, NS, SIP 40-40#, FP
20-20/20-20#

DST (5) 3585-3694(PENN, CGL)/30-30-
30-30, REC 30'M, NS, SIP 456-
497#, FP 40-40/62-62#

MICT - CO, PF (LKC) 3575-3582,
3536-40, 3518-24, 3492-98, SWB DWN
W/SO, NAT, AC 500 G (15% REG) INTO
EACH ZONE, ONFU 800'FL, SWB DWN &
REC 14 BF, 34% O, PF (PENN) 3598-
3606, (LKC) 3554-58, AC 500 G
(15% REG), SWB DWN & REC 1 BF, 16%
O/30", 2.61 BF, 25% O/60", 3.48 BF,
30% O/60", 2.32 BF, 32% O/60", 2.32
BF, 30% O/60", 2.20 BF, 39% O/60",
2.00 BF, 30% O/60", POP, P 59 BFPD,
31% O, COMMINGLED