

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21600-00-01
Spot: SESESW Sec/Twnshp/Rge: 12-10S-18W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BARDOT OWWO Well #: 1
County: ROOKS Total Vertical Depth: 4039 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3910		
DVT		1483		
PROD	4.5	4011	0	275 SX
SURF	8.625	277	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2006 10:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1483' w/550 sxs. CIBP 3910'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2006 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing - hit bridge at 1150' and 1700'.
Ran to 2170'. Allied pumped 180 sxs 60/40 pozmix - 10% gel with 300# hulls - cwc.
PTOH. Allied pumped 80 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside and instant pressure 500#.

Perfs:

Top	Bot	Thru	Comments
3630	3638		
3612	3616		
3597	3602		
3579	3584		
3559	3561		
3553	3555		
3541	3546		
3522	3525		
3516	3519		

INVOICED
2006 8-3-06
2007060308

RECEIVED
AUG 02 2006

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04


HM

Signed Richard Williams
(TECHNICIAN)

JUL 28 2006

PT

FRONTIER OIL COMPANY
 1720 KSB&T BUILDING #1 BARDOT 'OWWO' 12-10-18W
 WICHITA, KS 67202 SE SE SW
 CONTR RED TIGER DRILLING CO. CTY ROOKS
 GEOL RICHARD D. PARKER FIELD PLAINVILLE
 ELV 2153 KB SPD 9/15/82 CARD ISSUED 12/30/82 IP OIL WELL
 API 15-163-21,600-A LKC 3516-3616 OA



SMP	Tops	Depth Datum	
ANH	1485 +	688	OLD INFO: OPERATOR WAS FRONTIER OIL CO., #1 BARDOT, SPD 3.4 82, SET 8- 5'8 " 277 175SX, COMP AS D&A, SIMP 3/13/ 81, CARD ISSUED 4-8 82, CO'NTR. RED TIGER DRILLING, GEOL. JOEL A. ALBERTS DST (1) 3374-3530 (LKC) 50-30-60-30, REC 125' MW, SIP 1056-1056#, FP 104-145 104-124# DST (2) 3530-3552 (LKC) 60-30-60-30, REC 30' OCM, 32' SOCM, SIP 818-124#, FP 21-21 21-31# DST (3) 3552-92 (LKC) 60-30-0-0, REC 3' M, ISIP 83#, IFP 41-41# DST (4) 3592-3650 (LKC) 60-45-0-0, REC 5' M, ISIP 581#, IFP 45-45# DST (5) 3647-3720 (PENN, CGL, SIMP) / 60-30-30-30, REC 30' M, SIP 663-570#, FP 62-73 83-83#
BRNVLE	2922-	669	
TARK	2918-	765	
HOP	3091-	938	
TOP	3120-	967	
HEEB	3342-	1189	
TOR	3362-	1209	
LKC	3385-	1232	
B KC	3551-	1498	
CONG CHT	3561-	1508	
SIMP DOL	3730-	1577	
OTD	3736-	1583	
ARB	3750-	1597	
DDTD	4039-	1886	
LOGGED			

INDEPENDENT OIL & GAS SERVICE
 WICHITA

NEW INFO: RE-ENTERED 9/15/82, WSH DWN TO OTD, DDTD 4039', SET 4 1:2 " 4011/275SX, SET DV TOOL AT 1483/550SX; MICT - CO, DRLD DV TOOL, SWB DWN, PF (SIMP DOL) 3630-38 W/4 SPF, SET PLUG AT 3910', SWB DWN & REC 1.16 BF, TR' O / 1 HR, 1.16 BF, 10% O / 2ND HR, PF (LKC) 3612-16, 3597-3602 W/ 4 SPF, SET PLUG AT 3620', PF (LKC) 3579-84 W/4 SPF, SET PLUG AT 3590', SWB DWN, DRLD UP PLUG, PF (LKC) 3559-61, 3553-55, 3541-46 W/4 SPF, SET PLUG AT 3570', PF (LKC) 3522-25, 3516-19 W/4 SPF, SWB DWN, DROVE PLUG, SWB 2.96 BF, 25% O / 1 HR, 2.32 BF, 25% O / 2ND HR, 1.67 BF, 30% O / 3RD HR, T&R, POP