

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23977-00-00
Spot: SENESE Sec/Twnshp/Rge: 25-13S-18W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: GROSS Well #: 1
County: ELLIS Total Vertical Depth: 3661 feet

Operator License No.: 30553
Op Name: UNREIN, GLENN DBA UNREIN OIL CO
Address: 300 W. 40TH STREET
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		3580		
PROD	4.5	3610	0	100 SX
RBP		3020		2 SX SAND
SURF	8.625	260	0	150 SX

\$ 118.98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2006 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CHARLES D. FARR Company: UNREIN OIL COMPANY Phone: (785) 635-2920

Proposed Plugging Method: Fish at 1800'.
Perf at 1373' with 3 shots - 1745' with 3 shots - 726' with 3 shots.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2006 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Squeezed from 1650' to 1800' w/300 sxs.
Drilled out casing - squeezed and twisted tubing off at 1800'.
Tied to 4 1/2" casing - squeezed 275 sxs 60/40 pozmix - 10% gel with 300# hulls.
Max. P.S.I.250#. S.I.P. 250#.
Squeezed annulus to 300# P.S.I. with one sack of cement.
Total of 276 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

INVOICED
DATE 8-3-06
TEL. NO. 200 7060309

RECEIVED
AUG 02 2006
KCC WICHITA

Remarks: BASGALL TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

NO

JUL 27 2006

RF


CROWE DRILLING COMPANY, INC.
 1732 KSB&T BLDG #1 GROSS
 WICHITA, KS 67202

25-13-18W
 SE NE SE

CONTR RED TIGER DRILLING CTY ELLIS

GEOLOGICAL FRANK BROOKS FIELD YOUNGER NW

ELV 2081 K_BSPD 8/7/84 CARD ISSUED 1/31/85 IP TEMP ABD
 2076 GL



LOG	Tops	Depth/Datum	API 15-051-23,977
			8 5/8 " 260.32 / 150SX, 4 1/2 " 3610 / 100SX
ANH	1322+	759	DST (1) 3364-3400 (LKC) / 60-60-60-60, 90' GIP, REC 270' OCWM, SIP 448-448#, FP 27-170 / 213-213#, BHT 110°
TOP	3055-	974	(10DST (2) 3420-70 (LKC) / 30-30-30-30, 90' GIP, REC 150' OIL & WCM, 180' OIL & WCM, 60' SOCMW, SIP 437-437#, FP 106-127 / 181-181#, BHT 111°
HEEB	3316-	1235	DST (3) 3477-3540 (LKC) / 30-30-30-30, REC 125' SOCM, SIP 159-159#, FP 53-53 / 74-85#, BHT 112°
LANS	3361-	1280	DST (4) 3585-3613 (PENN, ARB) / 45-45-45-45, 45' GIP, REC 185' OIL & GCM, SIP 1054-1031#, FP 114-125 / 125-125#, BHT 110°
BKC	3591-	1510	
ARB	3608-	1527	
RTD	3613-	1532	

MAOICEN

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

NOTE: CORRECTION: 8/16/84 - ORIGINALLY FIRST REPORTED IN C NE SE