

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00520-00-00

Spot: SWSWSWNE

Sec/Twnshp/Rge: 11-31S-40W

2340 feet from N Section Line, 2340 feet from E Section Line

Lease Name: KELLER

Well #: 1

County: MORTON

Total Vertical Depth: 2512 feet

Operator License No.: 32787

Op Name: KANSAS NATURAL GAS OPERATING, I

Address: PO BOX 818 1200 MAIN STREET  
HAYS, KS 67601

String Size Depth (ft) Pulled (ft) Comment

CIBP 2350 WITH 2 SX CMT

PROD 7 2511 0 WITH 700 SX CMT

SURF 10.75 360 WITH 325 SX CMT

\$ 81.604

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 07/12/2006 8:00 AM

Plug Co. License No.: 99997

Plug Co. Name: HALLIBURTON ENERGY SERVICES

Proposal Rcvd. from: STEVE LEHNING

Company: KANSAS NATURAL GAS

Phone: (785) 625-7353

Proposed Plugging Method: SET CIBP @ 2350' WITH 2 SX CMT. PERFORATE AT 575'. CIRCULATE 200-300 SX CMT. TRY TO FILL 7" CASING INSIDE & OUT.

Plugging Proposal Received By: JIM HOLLAND

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/12/2006 12:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2350' WITH 2 SX CMT. PERFORATE AT 575'. PUMP 165 SX CMT DOWN 7" AT 575', NO CIRCULATION. PUMP 3 SX CMT DOWN 7" X 10 3/4" ANNULUS.


Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2474 | 2482 |      |          |
| 2454 | 2462 |      |          |
| 2412 | 2428 |      |          |
| 2388 | 2394 |      |          |

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

Plugged through: CSG

District: 01



Signed

Jim Holland DIRT II  
(TECHNICIAN)

RECEIVED  
JUL 28 2006  
KCC WICHITA

Form CP-2/3

Handwritten initials and signature.