

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-23016-00-00  
Spot: Sec/Twnshp/Rge: 23-26S-19E  
2534 feet from S Section Line, 2883 feet from E Section Line  
Lease Name: ROBERTS Well #: 7-R  
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.25	40	0	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2006 11:30 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION COMPANY Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 04/06/2006 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800PSI.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAY 17 2006 CPT

CHANUTE, KS

INVOICED  
DATE 0-15-06  
2006061805

Remarks: SPOT LOCATION ESTABLISHED BY GPS SURVEY AS SESSION POINT NO.37. (CPT 05/17/06)

Plugged through: CSG wave plugging fee as per clayton Titel

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED

MAY 25 2006

KCC WICHITA

CPT