

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23330-00-00

Spot: NWNESW

Sec/Twnshp/Rge: 23-26S-19E

2181 feet from S Section Line, 3884 feet from E Section Line

Lease Name: ROBERTS

Well #: 8-R

County: ALLEN

Total Vertical Depth: 600 feet

Operator License No.: 0

Op Name: LANDOWNER

Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.25	40	0	

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/28/2006 11:30 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY

Proposal Rcvd. from: MIKE WIMSETT

Company: W & W PRODUCTION COMPANY

Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 03/28/2006 12:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 250PSI. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

MAY 17 2006 CPT

CHANUTE, KS

INVOICED
DATE 6-15-06
TOTAL DOL 2006061805

Remarks: SPOT LOCATION ESTABLISHED BY GPS SURVEY AS SESSION POINT NO. 41. (CPT 05/17/2006)

Plugged through: CSG waive plugging fee as Per Clayton Titel

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED

MAY 25 2006

KCC WICHITA

Form CP-2/3

PCT