

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-22616-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 23-26S-19E  
2854 feet from S Section Line, 3305 feet from E Section Line  
Lease Name: ROBERTS AA Well #: 61AA  
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.25	20	0	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2006 1:30 PM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATEY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TOSQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/06/2006 2:20 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750 PSI.

RECEIVED  
KCC DISTRICT #3  
JUN 14 2006 CPT  
CHANUTE, KS

Perfs:

Remarks: SPOT LOCATION FOR THIS WELL ESTABLISHED AS GPS SESSION POINT NO. 29.

Plugged through: CSG

RECEIVED  
JUN 19 2006  
KCC WICHITA

District: 03

Signed Clayton P Titel  
(TECHNICIAN)

INVOICED  
DATE June 21, 2006  
INV. NO. 2006061818

ACT