

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-23017-00-00
Spot: NW NESW Sec/Twnshp/Rge: 23-26S-19E
2175 feet from S Section Line, 3547 feet from E Section Line
Lease Name: ROBERTS Well #: 10-R
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0
Op Name: LANDOWNER
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.5	40	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2006 11:30 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION COMPANY Phone: (620) 431-4132

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 03/28/2006 2:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 300PSI. 25 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 17 2006 CPT

CHANUTE, KS

DATE 6-15-06
2006061805

Remarks: SPOT LOCATIN ESTABLISHED BY GPS SURVEY AS SESSION POINT NO. 40. (CPT 05/17/2006)

Plugged through: CSG *wave plugging fee as per clayton titel per dist.*

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED

MAY 25 2006

KCC WICHITA

PCT