

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-22604-00-00
Spot: SWSENW Sec/Twnshp/Rge: 23-26S-19E
3031 feet from S Section Line, 3692 feet from E Section Line
Lease Name: ROBERTS AA Well #: 47 AA
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0
Op Name: LANDOWNER
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.25	20	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2006 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 03/29/2006 9:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 350 PSI. 25 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 31 2006

CHANUTE, KS

CPT

INVOICED
DATE 6-15-06
REF. NO. 2006061805

RECEIVED
JUN 06 2006
KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED AS GPS SESSION POINT NO. 32.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PET