

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-23329-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 23-26S-19E  
2491 feet from S Section Line, 3866 feet from E Section Line  
Lease Name: ROBERTS Well #: 1-R  
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.25	40	0	

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/28/2006 10:30 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/28/2006 11:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PLUGGED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600PSI. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAY 17 2006

CHANUTE, KS CPT

INVOICED  
DATE 6-15-06  
WEL. NO. 2006061805

Remarks: SPOT LOCATION ESTABLISHED BY GPS SURVEY (CPT 05/17/06)

Plugged through: CSG *waive plugging fee as per Clayton Titel.*

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
MAY 25 2006  
KCC WICHITA

Form CP-2/3

AKT