

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-22618-00-00  
Spot: SESENW Sec/Twnshp/Rge: 23-26S-19E  
2854 feet from S Section Line, 2883 feet from E Section Line  
Lease Name: ROBERTS AA Well #: 63AA  
County: ALLEN Total Vertical Depth: 600 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	600	0	
SURF	6.25	20	0	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2006 11:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 600' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 04/06/2006 11:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:  
THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750 PSI. 21 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:  
  
**RECEIVED**  
KCC DISTRICT #3  
MAY 31 2006 CPT  
CHANUTE, KS  
  
**INVOICED**  
DATE 6-15-06  
2006061805  
  
**RECEIVED**  
JUN 06 2006  
KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED AS GPS SESSION POINT NO. 28.  
Plugged through: CSG

District: 03 Signed Clayton P. Titel  
(TECHNICIAN)

*pkd*