

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: NF Producers
Address: PO Box 237
Phone: (785) 874-4827 Operator License #: 4472
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: July 14, 2006 (Date)
by: Jay Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing - K.C. Depth to Top: 3168' Bottom: 3289' T.D. 3460
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163-20914 - 00 - 00
Lease Name: Hrabe "A" KCC 8/3/06 PKT
Well Number: 5-26 Per CP-1 + ~~CP-2~~ CP-3
Spot Location (QQQQ): NE - NE - NW -
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 26 Twp. 8 S. R. 17 East West
County: Rooks
Date Well Completed: 5-12-79
Plugging Commenced: 7-18-06
Plugging Completed: 7-18-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing - K.C.	Oil	3121	3450	8 5/8	249'	
				4 1/2	3460'	


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tbg to 3085' - Spot 100 sx's 60/40 w/10% gel & 800# Hulls - Had good circ. on 4 1/2 & 8 5/8" - Pulled tbg to 1542', pumped 75 sx's & 200# Hulls, Cmt to sur. - Pulled tbg - Tied onto 4 1/2" squeezed 100 sx's to sur. - Circ. cmt on 8 5/8" - SI

Name of Plugging Contractor: NF Producers License #: 4472
Address: PO Box 237, Norton, KS 67654
Name of Party Responsible for Plugging Fees: Frickey Investment Management Co.
State of Colorado County, Jefferson, ss. Brett Hildebrand
PKT per operator Laura. **RECEIVED AUG 02 2006 KCC WICHITA**

(Employee of Operator or Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brett Hildebrand
(Address) PO Box 237, Norton, KS 67654



SUBSCRIBED and SWORN TO before me this 31st day of July, 20 06
Paula Strayer My Commission Expires: 01-03-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT