

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
JUL 31 2006

KCC WICHITA  
Form CP-4  
December 2003  
File or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: SunStone Operating Company, LLC  
Address: 101 N Robinson, Suite 810, Oklahoma City, OK 73102  
Phone: (918) 621-6533 Operator License #: 33802  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: July 5, 2006 (Date)  
by: Steve Durant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
n/a Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-171-20591-0000  
Lease Name: Grube  
Well Number: 21-1  
Spot Location (QQQQ): \_\_\_\_\_ - SW - SW - SW  
330 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 21 Twp. 18 S. R. 31  East  West  
County: Scott  
Date Well Completed: n/a Spud 4/24/05  
Plugging Commenced: 7/11/06  
Plugging Completed: 7/11/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4	330	0
				7-5/8	<del>4398</del> 3306	0
					KCC Pkt 8/1 8-1-06 Per CP 213	


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pump 16 sks Gel blended with 100# Cotton Seed Hulls. Pump 60 sks Cement blended with 300# Cotton Seed Hulls.  
POOH to 3118'. Pump 40 sks cement and POOH to 1012'. Pump 50 sks cement and POOH to 351'. Pump 70 sks cement  
circulated to surface. Fill 7-5/8" casing with 10 sks cement. Pump 20 sks cement down 10-3/4 - 7-5/8 annulus  
and pressure up to 700#

Name of Plugging Contractor: Allied Cementing License #: none assigned 99996 PKT  
Address: P O Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: SunStone Operating Company, LLC  
State of Oklahoma County, Tulsa, ss.

Robert A Klunder (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) R. Klunder  
(Address) P O Box 35888, Tulsa, OK 74153-0888

SUBSCRIBED and SWORN TO before me this 5th day of July, 2006  
[Signature] My Commission Expires: 2-1-08  
Notary Public

PKT