

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: New Donna Lee Oil Co.  
Address: 221 Fern Meadow Drive  
Phone: (661) 399-7294 Operator License #: 32596  
Type of Well: ENHR Docket #: E-10949  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 5/17/06 (Date)  
by: Allen Dunning (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Bartlesville Depth to Top: 1265 Bottom: 1273 T.D. 1335  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-125-01281-00-00  
Lease Name: Powell  
Well Number: 18  
Spot Location (QQQQ): \_\_\_\_\_ - NE - SE - SE  
850 Feet from  North /  South Section Line  
400 Feet from  East /  West Section Line  
Sec. 17 Twp. 34 S. R. 14  East  West  
County: Montgomery  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 5/17/06  
Plugging Completed: 5/17/06

Show depth and thickness of all water, oil and gas formations.

*KCC PET 8/3/06 PERKBDMS*

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surf	NA	8 5/8"	cemented to	surface
Bartlesville	oil and water	surf	1281'	4 1/2"	cemented to	surface
		surf	1236'	2 3/8"	cemented to	surface

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate 2 3/8" pipe @ 700', 350', and 150', ran in 1" pipe inside 2 3/8" to 1227', circulate cement to surface, pull 1" pipe out, top off w/cement. Well plugged.

Total cement used 137 sacks

Name of Plugging Contractor: Rick's Well Service License #: 33422

Address: P.O. Box 268, Cherryvale, KS 67335

Name of Party Responsible for Plugging Fees: New Donna Lee Oil Co.

State of Kansas County, Montgomery, ss.

Rick Housel - Agent

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Rick Housel - Agent

(Address) \_\_\_\_\_

SUBSCRIBED and SWORN TO before me this 27th day of July, 20 06

M. Denise Housel  
Notary Public

My Commission Expires: 8-11-2009



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

REC'D  
KCC DISTRICT  
JUL 28 2006  
CHANDLER, KS

*PET*

RECEIVED  
AUG 9 2 2006  
KCC WICHITA