

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tengasco, Inc.
Address: PO Box 458 Hays, KS 67601
Phone: (785) 625-6374 Operator License #: 32278
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-24-06 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3516 Bottom: 3638 T.D. 4039

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-21600-00-01
Lease Name: Bardot OWWO KCC PRT
Well Number: #1 8/1/06 PRT per CP213
Spot Location (QQQQ): C - SE - SE - SW
330 Feet from North / South Section Line
2970 Feet from East / West Section Line
Sec. 12 Twp. 10 S. R. 18 East West
County: Rooks
Date Well Completed: 11-23-82
Plugging Commenced: 7-24-06
Plugging Completed: 7-24-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & water	0	277'	8-5/8"		
		0	4011'	4-1/2"	9-17-82	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Tied onto 8-5/8" csg. Pres to 500 PSI. Ran 2-3/8" tbg to 2170'. Circ cmt to surface w/ 180 sx & 300# hulls. Pulled tbg.
Tied onto 4-1/2" csg. Squeezed in 60 sx cmt & 200# hulls to 1000 PSI. Total cmt 240 sx 60/40 poz containing 10% gel & 500# hulls.

Name of Plugging Contractor: Allied Cementing Tengasco, Inc License #: 32278 **RECEIVED**
Address: PO Box 31 Russell, KS 67665
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Ellis, ss.
Gary Wagner (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Wagner
(Address) PO Box 458 Hays, Ks 67601

SUBSCRIBED and SWORN TO before me this 28th day of July, 2006
Linda K Pfannenstiel My Commission Expires: 2/5/08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PRT