

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tengasco, Inc.
Address: PO Box 458 Hays, KS 67601
Phone: (785) 625-6374 Operator License #: 32278
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-24-06 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3473 Bottom: 3586 T.D. 3800'
Simpson Depth to Top: 3680 Bottom: 3682 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163-21996 - 00 - 00
Lease Name: Ross
Well Number: #2
Spot Location (QQQQ): C - SE - NE - NW
990 Feet from North South Section Line
2310 Feet from East West Section Line
Sec. 12 Twp. 10 S. R. 18 East West
County: Rooks
Date Well Completed: 6-1-83
Plugging Commenced: 7-26-06
Plugging Completed: 7-26-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & water	0	288'	8-5/8"	3-22-83	
Simpson	Oil & water	0	3787'	4-1/2" 5/2	4-1-83	
				KCC 8/1/06 PKT per cpr 213		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied onto 8-5/8" csg. Pres to 350 PSI.
Tied onto 4-1/2" csg. Mixed 185 sx cmt w/ 500# hulls. Squeezed to 500 PSI. Total cmt 185 sx 60/40 poz w/ 10% gel & 500# hulls
KCC 8/1/06 PKT Gary Wagner per oper

Name of Plugging Contractor: Allied Cementing Tengasco, Inc License # 32278
Address: PO Box 31 Russell, KS 67665
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Ellis, ss.
Gary Wagner


RECEIVED
JUL 31 2006
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 458 Hays, Ks 67601

SUBSCRIBED and SWORN TO before me this 28th day of July, 2006
Linda K Pfannenstiel My Commission Expires: 2/5/2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PKT