

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01440-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 18-9S-21W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SUTOR B Well #: 7  
County: GRAHAM Total Vertical Depth: 3846 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	1783		75 SX
PROD	5.5	3843	0	w/unknown sxs cmt \$ 125.00
SURF	8.625	165	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2006 2:30 PM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Squeezed at 900' - 1000' - 1300' - 1390'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2006 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 225 sxs cement with 500# hulls.  
Max. P.S.I. 800#. S.I.P. 500#.  
Hooked onto 4 1/2" x 5 1/2" annulus - instant pressure and 5 1/2" x 8 5/8" annulus - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3843	3846		OPEN HOLE

RECEIVED  
AUG 03 2006  
KCC WICHITA  
INVOICED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

DATE 8-4-06  
WV. NO. 2007060317

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

AUG 01 2006

PST

PEEL-HARDMAN

#7 SUTOR

NE SW SE

Contr.

GRAHAM Coun

E 2327

Comm.

Comp. 2-23-51 IP 2196 BOPD

Tops	Depth	Datum
ARB	3843	-1516
T.D.	3847	-1520

Casing

8" 165  
5" 3843

ACID 500  
SWB 20 BOPH

MOREL POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS