

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01438-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 18-9S-21W  
2310 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SUTOR B Well #: 5  
County: GRAHAM Total Vertical Depth: 3804 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3803	0	w/unknown sxs cmt
SURF	8.625	168	0	w/unknown sxs cmt

\$123.63

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2006 10:30 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Well squeezed at 131' - 295' w/150 sxs.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2006 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 150' - 1000' - 1850'.  
TIH with tubing to 3000' - mixed and pumped 65 sxs cement with 200# hulls.  
Pulled up to 2000' - spotted 65 sxs cement with 100# hulls.  
Pulled up to 1000' - circulated cement up 5 1/2" x 8 5/8" with 100 sxs cement and 200# hulls.  
POOH Swaged onto 5 1/2" and pumped 10 sxs cement.  
S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3803	3804		OPEN HOLE

RECEIVED  
AUG 03 2006  
KCC WICHITA  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED  
8-4-06  
DATE 2007060317  
INV. NO.

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)

AUG 01 2006

*PST*

PEEL-HARDMAN

#5

SUTOR

18-9-21W 22

NE NW SE

Contr.

GRAHAM

County

E 2299

Comm.

Comp.

12-29-50

IP


2000 BOPD

DRAW DOWN

Tops	Depth	Datum
REW ARB	3797	-1498
ARB	3800	-1501
T.O.D.	3804	-1505

Casing  
 8" 168 . 250' 01H/1 HR:  
 5" 3803 ACID 500: SWB 30  
 BOPH/4 HRS

MOREL POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS