

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20591-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 21-18S-31W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: GRUBE Well #: 21-1  
County: SCOTT Total Vertical Depth: 4678 feet

Operator License No.: 33802  
Op Name: SUNSTONE OPERATING COMPANY, L  
Address: 101 N. ROBINSON, SUITE 810  
OKLAHOMA CITY, OK 72102

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1681		WITH 400 SX CMT
L1	5.5	4579		WITH 400 SX CMT
PROD	7.625	3306	0	WITH 600 SX CMT
SURF	10.75	334		WITH 270 SX CMT

\$ 152.04

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2006 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BILLIE GRIGGS Company: SUNSTONE ENERGY Phone: (405) 605-1274

Proposed Plugging Method: RUN TUBING TO 4500'. MIX & PUMP 20 SX GEL, 400# HULLS, 50 SX CMT. PLUG AT 3100' WITH 50 SX CMT. PLUG AT 1700' WITH 75 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 60' CIRCULATE CMT TO SURFACE. PRESSURE TEST 7 5/8" X 10 3/4" ANNULUS TO 500 PSI. 50 SX CMT TO PUMP.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/11/2006 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 1600# GEL WITH 100# HULLS & 75 SX CMT WITH 300# HULLS. FULL CIRCULATION. 1ST PLUG AT 3118' WITH 40 SX CMT. 2ND PLUG AT 1709' WITH 60 SX CMT. 3RD PLUG AT 1011' WITH 50 SX CMT. 4TH PLUG AT 350' TO 0' WITH 70 SX CMT. GOOD CIRCULATION ON ALL PLUGS. TRIP OUT OF HOLE WITH TUBING. TOP OFF 7 5/8" CASING WITH 10 SX CMT. PUMP 20 SX CMT DOWN 7 5/8" X 10 3/4" ANNULUS TO 700#.

Perfs:


Top	Bot	Thru	Comments
4579	4678	OH	

INVOICED  
DATE 8-4-06  
WT. NO. 2007060319

RECEIVED  
AUG 03 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.  
Plugged through: TBG

District: 01



Signed Ken Jehlik (TECHNICIAN)

Form CP-38  
PET