

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-21534-00-00  
Spot: NENENE Sec/Twnshp/Rge: 5-23S-35W  
125 feet from N Section Line, 150 feet from E Section Line  
Lease Name: GRAY B SWD Well #: 1  
County: KEARNY Total Vertical Depth: 1724 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	1707	0	
SURF	5.5	1031		

\$ 56.03

Well Type: SWD UIC Docket No: D27301.0 Date/Time to Plug: 07/19/2006 8:00 AM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA PRODUCTION Phone: (620) 356-6955

Proposed Plugging Method: PUMP 61 SX CMT & 150# HULLS ON BOTTOM. PUMP 11 SX CMT DOWN 2 3/8" TUBING. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/19/2006 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 61 SX CMT & 150# HULLS FOR BOTTOM PLUG. WAIT 5 HOURS. PUMP 11 SX CMT DOWN 2 3/8" TUBING. PRESSURE TO 200# & HELD. PUMP 2 SX CMT DOWN 2 3/8" X 5 1/2" ANNULUS. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
1612	1707		

INVOICED


DATE 8-4-06  
WZ. NO. 2007000300

RECEIVED  
AUG 03 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

Plugged through: CSG

District: 01



Signed Ken Jehlik  
(TECHNICIAN)

Form C

PET