

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - Drilled in 1952 15-055-00666-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date Spud: September 17, 1952.

Well Operator: Kansas Natural Gas Operating, Inc. KCC License #: 32787
(Owner / Company Name) (Operator's)

Address: P.O. Box 815 City: Sublette

State: Kansas Zip Code: 67877 Contact Phone: (620) 675 - 8185

Lease: Ohmes Well #: 2 Sec. 23 Twp. 26 S. R. 32 East West

SE - SE - NW - 1/4 Spot Location / QQQQ County: Finney

1980' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2140' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: None Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 562' Cemented with: 275 Sacks

Production Casing Size: 5 1/2" - 14# Set at: 2736' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: Herrington perforated at 2678' - 2696'. Krider perforated at 2700' - 2718'.

Elevation: 2884' (G.L. / K.B.) T.D.: 2760' PBTD: 2736' Anhydrite Depth: 1850'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Run cement bond log from 1200' to top of cement on 5 1/2". Set cast iron plug at 1430' approx. Dump (2) sacks cement on top plug w/bailor. Locate top of cement behind production pipe & perforate (4) holes in casing at that point. Attempt to circulate cement w/ 80 sacks over casing capacity to fill inside & outside of production pipe. Hook onto annulus & try to circulate. Cut well off 6' below ground, weld cap & backfill to complete. KCC - Mr. Jim Holland

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Have no well logs on file. Records are minimal.

RECEIVED

JUL 27 2006

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Steve Lehning, Supt.
for Kansas Natural Gas Operating, Inc. Phone: (620) 675 - 8185

Address: P.O. Box 815 City / State: Sublette, KS 67877

Plugging Contractor: Halliburton KCC License #: 5287 99997
(Company Name) (Contractor's)

Address: Liberal, Kansas Phone: (800) 853 - 3555

Proposed Date and Hour of Plugging (if known?): Not known - Depends on Halliburton Availability

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-27-06 Authorized Operator / Agent: Steve Lehning, Supt. For Kansas Natural Gas Operating, Inc.
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Kansas Natural Gas Operating, Inc.
PO Box 818
1200 Main Street
Hays, KS 67601

August 03, 2006

Re: OHMES #2
API 15-055-00666-00-00
SENW 23-26S-32W, 3300 FSL 3140 FEL
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely

David P. Williams
Production Supervisor