

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Eason Drilling and Services
Address: Two West Second St., Tulsa, Ok. 74103
Phone: (918) 591-1688 Operator License #: 30151
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: April 14, 2006 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2945' Bottom: 3265' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 6678'

API Number: 15-119-203390000
Lease Name: Adams
Well Number: 1-22
Spot Location (QQQQ): C - SE - SE - NW
2310' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 22 Twp. 34 S. R. 29 East West
County: Meade
Date Well Completed: 1/17/79
Plugging Commenced: 4/17/06
Plugging Completed: 04/18/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Council Grove (7')	Gas	2945'	2952'	8 5/8'	1506'	0'
Council Grove (7')	Gas	3055'	3062'	4 1/2"	3420'	2200'
Council Grove (5')	Gas	3219'	3224'			
Council Grove (6')	Gas	3260'	3266'			


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Displaced hole with mud. Set CIBP @ 2900' with 2 sks cmt on top. Recovered 2200' of 4 1/2" casing. Placed plugs as follows: 50 sxs cmt 1530'-1330', 50 sxs cmt 690'-490', 10 sxs cmt 40'-0' with mud spacing each plug. Cut surface casing off 4' below ground level and welded on steel ID plate.
Plugging operations witnessed and approved by Kansas Corporation Commission field rep. Rick Stapleton.

Name of Plugging Contractor: Sargent and Lillard Casing Pulling Inc. License #: 32833
Address: P.O. Box 1450 Woodward OK. 73802

Name of Party Responsible for Plugging Fees: Eason Drilling and Service Co.
State of Oklahoma County, Tulsa, ss.

Steven Bleem (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Steven Bleem

(Address) Two West Second St., Tulsa, Ok. 74103

SCRIBED and SWORN TO before me this 2nd day of AUGUST, 2006

Tenna A. Johnson My Commission Expires: 4-4-07
Notary Public

RECEIVED

AUG 04 2006

KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ACT