

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/24/06 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4411 Bottom: 4419 T.D. 4419

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-21,133-00-00
Lease Name: Putnam B
Well Number: #3
Spot Location (QQQQ): _____ - _____ - NE - SW
1980' Feet from ☐ North / ☒ South Section Line
3300' Feet from ☒ East / ☐ West Section Line
Sec. 36 Twp. 20S S. R. 26W ☒ East ☒ West
County: Ness
Date Well Completed: 1/16/76
Plugging Commenced: 7/25/06
Plugging Completed: 7/26/06

KCC
8/17/06
PKT
per
CP2/3

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|------------|--|-------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Mississippi | oil and sw | 4411' | 4419' | 8-5/8" | 299' | none |
| | | | | 4-1/2" | 4411' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 2-3/8 tbg to 2033'. Swift Services spot 30 sx multidensity cement plug. Pull tbg up to 1412'. Spot 50 sx Class A, 3% cc, plug. Pull tbg to 692. Wt 1 hr.

Reload tbg, fluid down 250'. KCC field guy okayed. Pull tbg. Tag cmt w/perf gun @ 2025', middle plug gone. Mike Maier @ KCC said to proceed.

4 way perms @ 1000'. Swift Services: Pmp into holes @ 7 BPM @ 700#, no blow @ surf. Mix & pump 80 sx 60/40 Pozmix, 6% gel, 2 sx hulls, 70 sx cmt. SI csg.

Tie onto backside. Mix & pump 150 sx 60/40 pozmix, 6% gel. Pres up to 400# SI @ 300#. Tag cmt ins of csg @ 350'. Top off w/40 sx.

Name of Plugging Contractor: North Fork Well Service, LLC License #: 32938

Address: 7 SW 26th Avenue, Great Bend, KS 67530

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Casey Coats
(Employee of Operator) or (Operator) on above-described well, being first duly
sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the
same are true and correct, so help me God.

(Signature) Casey Coats


(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

RECEIVED
AUG 03 2006
KCC WICHITA

SUBSCRIBED and SWORN TO before me this 1st day of August

Michelle D. Henning
Notary Public

My Commission Expires



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT