

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

AUG 07 2006

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

055-00483-00-00

Lease Operator: Kansas Natural Gas Operating, Inc. Address: P.O. Box 815, Sublette, KS 67877 Phone: (620) 675-8185 Operator License #: 32787 Type of Well: Gas-Hugoton Docket #: NA The plugging proposal was approved on: July 3, 2006 by: Mr. Ken Jehlik Is ACO-1 filed? No If not, is well log attached? Yes Producing Formation(s): List All (if needed attach another sheet) Herrington Depth to Top: 2434' Bottom: 2478' T.D. Krider Depth to Top: 2502' Bottom: 2522' T.D. Winfield Depth to Top: 2552' Bottom: 2592' T.D.

API Number: 15 - Drilled in 1947 Lease Name: Finnup Well Number: 1 Spot Location (QQQQ): App. - Cen. - NE - 1/4 3960 Feet from North / South Section Line 1320 Feet from East / West Section Line Sec. 19 Twp. 24 S. R. 34 East West County: Finney Date Well Completed: January 12, 1947 Plugging Commenced: August 2, 2006 Plugging Completed: August 2, 2006

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Fresh Water, Herrington, Krider, and Winfield.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Ran in hole & set cast iron plug over perfs at 2408'. Used wireline bailor to spot (2) sacks cement on top of plug. Hook onto 7" casing and load hole to check for leaks. Pressured hole up to 200#. Perforate (4) holes at 1,000'. Pumped total of (220) sacks of 60/40 POZ down 7" casing. Hook onto backside & pumped (2) sacks & pressured up to 200#. Cut wellhead off and cap 6' below ground level. KCC Rep: Mr. Ken Jehlik

Name of Plugging Contractor: Halliburton License #: 5287 99997 Address: Liberal, Kansas

KCC 8/8/06 PER PER RBDms

Name of Party Responsible for Plugging Fees: Kansas Natural Gas Operating, Inc. State of Kansas County, Haskell, ss.

Steve M. Lehning @ Kansas Natural Gas Operating, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Steven M. Lehning, Supt. (Address) P.O. Box 815, Sublette, KS 67877

SUBSCRIBED and SWORN TO before me this 4th day of August, 2006

Notary Public signature and name

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT