

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED AUG 07 2006 KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Berexco, INC.

Address: PO Box 723 Hays, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7-25-06 (Date)

by: Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ARB Depth to Top: 3803 Bottom: 3804 T.D. 3804

API Number: 15-065-01438-00-00

Lease Name: Sutor B

Well Number: 5

Spot Location (QQQQ): NE - NW - SE - 8/8/06 2310 Feet from North / South Section Line per CP 2/3

1650 Feet from East / West Section Line

Sec. 18 Twp. 9 S. R. 21 East West

County: Graham

Date Well Completed: 11-50

Plugging Commenced: 7-25-06

Plugging Completed: 7-26-06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: ARB, oil, 0, 167, 8-5/8, 11-50, -. Row 2: ARB, oil, 0, 3803, 5-1/2, 11-50, -.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Rig up Perf-Tech. Perforate 2 holes each @ 1850', 1000', 150'. Run 2-3/8 open end tbg to 3000'. Rig up Allied Cementing. Mix 65 sxs 60/40 poz 10% gel w/ 300# hulls. Pull tbg to 2000' mix 65 sxs 60/40 poz 10% gel 200# hulls. Pull tbg to 1000'. Circulate cement to surface in 5-1/2x2-3/8 annulus w/ 100 sxs cement & 200# hulls. Pull tbg out of hole. Tie to 8-5/8 surface pipe - pressure to 400# - held. Tie to 5-1/2 csg. Mix 10 sxs cement, pressure to 500#. Shut in well.

Name of Plugging Contractor: Berexco, INC. License #: 5363

Address: PO Box 723 Hays, KS 67601


Name of Party Responsible for Plugging Fees: Dennis Kirmer Berexco, Inc

State of KS County, Ellis, ss. (KCC per 8/8/06 per Shanna Cooper)

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dennis Kirmer

(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 4 day of August, 2006. My Commission Expires: 9-19-09 Notary Public Shanna Miller