

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19389-00-00
NE NW SW Sec/Twp/Rge Sec 30 T28S R17E
2107 GPS feet from south section line
4173 GPS feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Carter OW1Operator: State Of Kansas Fee FundCounty WilsonName & Carter Lease ProjectWell Total Depth 1000 (est) feet

Address _____

Production Pipe: N/A Size Feet N/AAB oil well XXXXXX Gas Well _____Surface Casing: 8 Size Feet N/A

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K W Oil Well Service, IncLic. # 3097Address: 19450 Ford Road, Chanute, KS 667720Company to plug at: _____ Hour: _____ Day: 27 Month: 6 2006Plugging proposal received from: Jim KopleyCompany Name: K W Oil Well Service, Inc

Phone: _____

Were: _____

Actual Plugging Report: A one inch cement string was run to 30 ft and washed to 80 ft where rocks were encountered. The drilling rig was moved on location and the well drilled down to 145 ft to "iron". This iron was drilled thru to 165 ft. A rag packer was constructed on 2 inch pipe. The rag packer was lowered to 165 ft.

(continued below)

Plugging Proposal Received by:

Alan M. Dunning

Plugging attended by Agent:

All _____

Part _____

TECHNICIAN

None XXXXXXOperations Completed: Hour: _____ Day: 28 Month: 6 2006

Actual Plugging Report:

(continued from above) A one inch cement string was run outside the 2 inch

pipe to just above (150 ft) the rag packer. The rag packer was cemented-in using the one inch cement string.

A one inch cement string was run inside the 2 inch pipe to 150 ft. Cement was pumped thru this one inch pipe (located inside the 2 inch pipe), from 150 ft to surface. The one inch cement strings were removed. The 2 inch pipe at wellhead was hooked onto and additional cement squeezed into well and then shut in with 575 psi. A total of 87 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control # 20060061-001(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

RECEIVED
JUL 19 2006
KCC WICHITA

Signed:

Alan M. Dunning
TECHNICIAN

pgt