

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22368-00-00
Spot: NESWNE Sec/Twnshp/Rge: 11-14S-15W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DUMLER C Well #: 17
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S. YALE #609
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3349	0	125 SX CMT
SURF	8.625	603	0	240 SX CMT

\$ 108.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2006 1:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 07/10/2006 4:30 PM

WitnessType: COMPLETE (100%)
KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2100'.
Pumped 100 sxs 60/40 pozmix - 10% gel with 500# hulls.
Pulled to 1050' - circulated with 125 sxs with 100# hulls.
POOH. Tied onto casing and pumped 60 sxs cement.
Backside circulated and shut in - pumped 40 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3311	3313		
3291	3293		
3079	3083		
3067	3070		

RECEIVED
AUG 07 2006
KCC WICHITA

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

Signed _____

Case Morris
(TECHNICIAN)

INVOICED


8-8-06

2007060332

AUG 01 2006

PKT

ROY VONFELDT
 524 ST. JOHN #17 DUMLER 11-14-15W
 RUSSELL, KS 67665 NE SW NE
 CONTR VONFELDT DRILLING CO. CTY RUSSELL
 GEOL D. RIDER & H. DEINES FIELD GORHAM
 ELV 1878 KB SPD 5/29/84 CARD ISSUED 7/19/84 IP P 40 BO & 50 BWPD
 1873 GL ARB 3311-3313



LOG	Tops	Depth/Datum	API 15-167-22,368
ANH	908 +	970	8 5/8 " 603 / 240SX, 5 1/2 " 3349 / 125SX
B/ANH	946 +	932	MINOR SFO, NO ODOR IN LM FROM 2775-90, 2945-60
TOP	2763-	885	LIGHT ODOR, NSFO IN LM FROM 3068-70, 3078-84
HEEB	2986-	1108	FAIR ODOR & MINOR SFO IN LM FROM 3097-3100
TOR	3006-	1128	VERY LIGHT ODOR & MINOR SFO IN LM FROM 3116-20, 3126-30
LANS	3042-	1164	LIGHT ODOR & MINOR SFO IN LM FROM 3142-48, 3158-60
BKC	3270-	1392	NO ODOR & VERY MINOR SFO IN LM FROM 3225-30, 3255-58
ARB	3289-	1411	FAIR GSY ODOR & VERY MINOR SFO IN LM FROM 3272-76
PBTD	3349-	1471	GD ODOR & GSFO IN DOL FROM 3289-3302
LTD	3349-	1471	FAIR SHOW GSY FO IN QTZ SD FROM 3310-20
RTD	3350-	1472	FAIR ODOR & FAIR SHOW FREE GSY OIL & GD STN IN DOL FROM 3320-45
			NO CORES OR DSTS
			MICT - CO, PF (ARB) 3311-3313, AC 150G (15%), SWB LD, SO, SET 2 1/2 " TBG AT 3340, POP, P 40 BO & 50 BWP, (GR 36°), 6/19/84

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

NOTE: CORRECTION 6/21/84 - ORIGINALLY FIRST REPORTED AS #16 DUMLER