

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00723-00-00  
Spot: S2NE Sec/Twnshp/Rge: 3-11S-21W  
3300 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: HEDSTROM Well #: 3  
County: TREGO Total Vertical Depth: 3668 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3661	0	100 SX CMT
SURF	8.625	221	0	135 SX CMT

\$ 119.21

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/02/2006 2:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 300 sxs Swift Multi-Density Cement with 500# hulls.  
Ran tubing with scrapper - stacked out 694'. Pulled and ran notch collar in dry mud and cuttings. Got to 700' - no change - decided to P&A.  
Squeezes at 930' - 960' w/250 sxs in 1957'; 1238' - 1253' w/250 sxs in 1981'.  
Fluid level at 200'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/02/2006 6:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 700'. Swift pumped 40 sxs neat Swift Multi-Density Cement - cwc.  
PTOH. Swift pumped 60 sxs cement - circulated out 8 5/8" - shut in - followed with 100 sxs cement with 50# hulls.  
Max. P.S.I. 350#.  
Blew hole in 5 1/2" casing collar.  
Casing full of cement.

Perfs:

Top	Bot	Thru	Comments
3661	3668	OH	Completion

RECEIVED  
AUG 07 2006

Remarks: SWIFT SERVICES, INC.

KCC WICHITA

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED  
DATE 8-8-06  
TEL. NO. 2007060333

Form CP-2/3

AUG 04 2006

PKT

HARRY GORE

#3 HEDSTROM

3-11-21W  
C S2 NE

Contr. VEEDER SUP & DEV TREGO County

E. 2096RB Comm. 11-12-55 Comp. 12-23-55 IP 344 BOPD, NW

Tops	Depth	Datum
ANH	1539	557
TOP	3116	-1020
HEEB	3323	-1227
TOR	3341	-1245
LANS	3362	-1266
B/KC	3591	-1495
ARB	3660	-1564
TD	3668	-1572

Casing  
 8" 221  
 5" 3661  
 DST 3429-51/1/2 HR, 230' SW,  
 BHP 1250#  
 DST 3555-88/1 HR, 70' WTRY  
 MUD, BHP 1045#  
 DST 3661-68/1 HR, 1290' OIL,  
 BHP 990#  
 CO: PMP 50 B0/3 HR:

WHITE SW

+	+	+
+	+	+
+	+	+

(JIMMY DANIELS,  
GEOL)

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

11-12-55