

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20183-00-00
Spot: NWSE Sec/Twnshp/Rge: 12-3S-14E
1880 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GEORG Well #: 10-12
County: NEMAHA Total Vertical Depth: 2722 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2702	1018	205 SX CMT
SURF	8.625	260		133 SX CMT

\$ 88.47

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/16/2006 8:00 PM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2656' TO 2524' CEMENT FROM 2524' TO 2270' GEL FROM 2270' TO 300' CEMENT FROM 300' TO SURFACE,

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 01/19/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-16-06 ran tubing and tagged bottom at 2599'. Spotted 1.5 barrels of gel at 2599' and pulled tubing up to 2536'. Pumped 30 sacks of cement with 1 sack of cottonseed hulls and 47 barrels of gel. Had cement from 2536' to 2270' and gel from 2270' to 300'. Returned to the well on 1-19-06 and shot the casing off at 1018' and then pulled the casing to 298' and circulated 85 sacks of cement from 298' to surface and pulled the casing.

Perfs:

Top	Bot	Thru	Comments
2472	2474		
2403	2405		
2386	2387		
2374	2376		
2333	2335		
2320	2322		

RECEIVED
KCC DISTRICT

JUL 25 2006 TCH

CHANUTE, KS

RECEIVED
AUG 04 2006
KCC WICHITA

INVOICED

DATE 8-7-06
200706032

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor Herman

(TECHNICIAN)

PET