

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20184-00-00
Spot: SWSE Sec/Twnshp/Rge: 12-3S-14E
580 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GEORG Well #: 15-12 WD
County: NEMAHA Total Vertical Depth: 4183 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4076	818	443 SX CMT
SURF	8.625	283		162 SX CMT
T1	2.875	4028		

\$135.95

Well Type: SWD UIC Docket No: D28324.0 Date/Time to Plug: 01/16/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 4031; TO 4233;. CEMENT FROM 4233' TO 4026' GEL FROM 4026' TO 300'. CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 01/19/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

On 1-16-06 ran tubing and tagged bottom at 4180' and pumped 80 barrels of gel but hold would not load. Pumped 50 sacks of cement with 1 sack of cottonseed hulls and pulled the tubing to 3607' and waited for one hour. Ran tubing to 3702' and pumped 81 barrels of gel then pulled the tubing to 818' and shot the casing off. Had cement from 4180' to 3723' and gel from 3702' to 300'. Returned to the well on 1-19-06, pulled casing to 292' and circulated 85 sacks of cement from 292' to surface then pulled the casing.

Perfs:

Top	Bot	Thru	Comments
4076	4183		

INVOICED
8-7-06
2007060307

RECEIVED
AUG 04 2006
KCC WICHITA

RECEIVED
KCC DISTRICT #3
JUL 25 2006 TCH
CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed Taylor Citterman
(TECHNICIAN)

PKJ