

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05407-00-00
Spot: W2SENE Sec/Twnshp/Rge: 3-15S-13W
3300 feet from S Section Line, 990 feet from E Section Line
Lease Name: SHAFFER Well #: 7
County: RUSSELL Total Vertical Depth: 2385 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2380	0	w/unknown sxs cmt
SURF	10.75	488	0	w/unknown sxs cmt <u>\$ 77.51</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2006 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2006 11:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1350' - 675' - 150'.
Ran tubing to 1400'. Circulated with 210 sxs 60/40 pozmix - 10% gel cement with 100# hulls.
POOH Tied onto 7" casing - pumped 120 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

RECEIVED
AUG 07 2006
KCC WICHITA

INVOICED
DATE 8/8/06
200 7020338

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

140.

Signed

Case Morris

(TECHNICIAN)

AUG 01 2006

PKT

S A RUDIGER, ETAL #7 SCHAFFER 3-15-13W
W2 SE NE

Contr. LOUIS MAI DRILLING RUSSELL County

E 1843 Comm. 9-30-54 Comp. 10-29-54 IP 2,000,000 CFG

Tops	Depth	Datum
TARK	2265	-422
TD	2385	-542

Casing
10" 488
7" 2380

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS