

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-40037-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 23-14S-13W
589 feet from S Section Line, 3229 feet from E Section Line
Lease Name: BOND B Well #: 6
County: RUSSELL Total Vertical Depth: 3240 feet

Operator License No.: 6622
Op Name: SCHOENBERGER, J.L. DBA JASON OIL
Address: 363 W 12TH STREET PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	3224	0	125 SX	\$105,30
SURF	8.625	469	0	w/unknown sxs cmt	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2006 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JAMES SCHOENBERGER Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-8027

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2006 4:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 1500'.
Circulated with 180 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
POOH. Tied onto casing and pumped 70 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.
Well had been squeezed at 250'.

Perfs:

Top	Bot	Thru	Comments
3685	3689		
3042	3045		
2925	2942		
2921	2925		
2273	2276		
2251	2256		

RECEIVED
AUG 07 2006
KCC WICHITA

INVOICED

8/8/06
2007060339

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

PD.

Signed

Case Morris

(TECHNICIAN)

JUL 31 2006

Pkt



MAJICEP

12-249 MAP NO. _____

STATE Kans COUNTY Russell SEC 23-14S-13W

OPER R.P. Nixon - Russell, Kansas LOC 100' SE of C SE SW

WELL 6 FARM Bond "B"

POOL Hall Gurney ELEV 1751 GR 1754 1756

CONT L.J. Dreiling & Sons GEOL. _____

CO 3200' Oil Test

INT _____

FR 11-14-63^{SPUD} 11-13-63 COMP 12-24-63

TD 3225 FM Arbuckle PBTD 3050

PRODUCING FM. FROM TO PER/TREATMENT

Tark 2251-2278 40 Frac's

Lans 2921-25 16 3000A & Frac

Co P 25 BOPD + 30 BOPD (Gr NA) - Commingled

No surf set 5 1/2" csg cem to surf #3224 w/125 sx.

Data Inc.

(KB Spl)					
GH	2244	- 488	Hb	2824	-1068
1st Tark	2253	- 497	Tor	2841	-1085
Dov lm	2268	- 512	IKc	2893	-1137
2nd Tark	2271	- 515	No BKc	called	
3rd Tark	2354	- 598	Arb	3210	-1454
Top	2589	- 833	RTD	3225	-1469