

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15740-00-00  
Spot: N2NESW Sec/Twnshp/Rge: 12-16S-12W  
2256 feet from S Section Line, 3426 feet from E Section Line  
Lease Name: WEBER Well #: 6  
County: BARTON Total Vertical Depth: 3292 feet

Operator License No.: 6357  
Op Name: WEBCO OIL CO., INC.  
Address: 2136 NE 90 AVE.  
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3220		
PROD	7	3290	0	
SURF	10.75	402	0	\$ 106.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2006 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: NICK WEBER Company: QUALITY WELL SERVICE, INC. Phone: (620) 587-3539

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 05/11/2006 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 750' and 150'.  
Ran tubing to 2700' - pumped 50 sxs 60/40 pozmix - 10% gel cement.  
Pulled to 2250' - pumped 24 sxs gel.  
Pulled to 750' and circulated with 150 sxs cement.  
POOH. Tied onto 7" and pumped 100 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3369	3371		
3295	3298		
3128	3138		
3110	3116		
3059	3063		
2861	2866		

**INVOICED**  
DATE: 8/8/06  
NO. 200.7060341

RECEIVED  
AUG 07 2006

Remarks: QUALITY CEMENTING.

KCC WICHITA

Plugged through: TBG

District: 04

100

Signed

Case Morris

(TECHNICIAN)

AUG 04 2006

PKT