

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20597-00-01
Spot: SWSNW Sec/Twnshp/Rge: 33-31S-12W
2310 feet from N Section Line, 1650 feet from W Section Line
Lease Name: ADAMS Well #: 2
County: BARBER Total Vertical Depth: 4325 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 150 N. MAIN, STE 801
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4324	2555	WITH 350 SX CMT
SURF	8.625	410		WITH 300 SX CMT

\$140,56

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/19/2006 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: NATHAN WOOD Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND OFF TO 3600' & 4 SX CMT. PLUG AT 600' WITH 65 SX CMT. PLUG AT 40' WITH 10 SX GEL FOR SPACER. 10 SX GEL

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2006 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3600' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 740' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4238	4250		
3954	3959		
3676	3684		

INVOICED
DATE 8-10-06
2007060352

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.


Plugged through: CSG

RECEIVED

AUG 09 2006

KCC WICHITA

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-2/3

[Handwritten signature]
[Handwritten initials]