

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20562-00-00
Spot: E2NESW Sec/Twnshp/Rge: 10-15S-15W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: POLCYN Well #: 5
County: RUSSELL Total Vertical Depth: 3320 feet

Operator License No.: 6772
Op Name: WEIGEL, V. FRANCIS - FAMILY PARTN
Address: PO BOX 219
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	3319	0	w/125 sxs cmt	\$ 107.90
SURF	8.625	265	0	w/200 sxs cmt	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2006 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID FUNK Company: QUALITY WELL SERVICE, INC. Phone: (785) 324-1041

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2006 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1600' - 880' - 250'.
Ran tubing to 1800' - pumped 125 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Pulled to 900' - circulated with 180 sxs cement.
POOH. Tied onto casing - pumped 65 sxs cement.
Backside circulated with cement.

Perfs:

Top	Bot	Thru	Comments
3252	3256		
3227	3230		
3220	3222		
3203	3206		
3182	3186		
3118	3120		
3110	3112		
3066	3068		

RECEIVED
AUG 07 2006
KCC WICHITA

INVOICED

DATE 8/8/06
2007060342

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

10.

Signed Case Morris
(TECHNICIAN)

AUG 01 2006

PKT

replacement card

V FRANCIS WEIGEL
GORHAM KS 67640

10-15S-15W
70'W, C E/2 NE SW

5 POLCYN

site: 8 N & 1/2 W OF GALATIA KS
contr: SHIELDS DRILLING
geol: R P NIXON

cty: RUSSELL
field: DONOVAN

API 15-167-20562

fr date 09/14/72 spd date 09/21/72 drig comp 09/21/72 card issued 11/30/72 last revised 12/21/98

ELV: 1803 KB, 1798 GL SMP

tops.....	depth/datum
SC.....	864 + 939
B/SC.....	898 + 905
TOP.....	2756 - 953
HEEB.....	2981 - 1178
TOR.....	2999 - 1196
LANS.....	3043 - 1240
BKC.....	3274 - 1471
CONG.....	3282 - 1479
ARB.....	3298 - 1495
RTD.....	3320 - 1517

IP status:
OIL, LKC, INTV NA , 11/23/72
CORR & INFO REL: 12/21/98 - ORIG FR 660'FNL & 400'FEL, NE/4; CORR DATES & CSG; ADDED MISC INFO
CSG: 8-5/8" 265 / 200 SX, 5-1/2" 3319 / 125 SX
COMMENT: NO OH LOG RUN; R/A LOG RUN 10/7/72;
REDESCRIBED LOC - IS ALSO 660'FNL & 400'FEL, SW/4
DRLR SD ZNS: 0-205 (W/SH), 205-325 (SH, W/SD), 325-864 (SD, W/SH & RED BEDS)

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)