

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21954-00-00
Spot: NESENE Sec/Twnshp/Rge: 1-15S-14W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: ULRICH A Well #: 1
County: RUSSELL Total Vertical Depth: 3191 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	3059	0	150 SX	\$ 103.71
SURF	8.625	357	0	275 SX	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2006 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: GARY YOUNGER Company: QUALITY WELL SERVICE, INC. Phone: (316) 681-2542

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2006 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Pumped 50 sxs 60/40 pozmix -10% gel cement with 500# hulls, followed with 20 sxs gel, followed with 100 sxs cement.
Max. P.S.I. 1000#. S.I.P. 600#.
Pumped 75 sxs cement down backside.
Max. P.S.I. 400#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
2900	2907		

INVOICED
DATE 8/8/06
2007060344
RECEIVED
AUG 07 2006
KCC WICHITA

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

JUL 31 2006

YOST OIL OPERATIONS
BOX 811

#1 "A" ULRICH

1-15-14W
SE NE NE

RUSSELL, KS 67665

CONTR BIG THREE DRILLING CTY RUSSELL

GEOLOGICAL BLOND FARMER FIELD TRAPP

E 1736 KB CM 7/24/82 ^{CARD} ISSUED 11/24/82 IP P 35 80 & 30 BWPD
SHAW(DOUG) 2900-07

API 15-167-21,954

-	+	+	+
+	+	+	+
-	+	+	+

LOG	Tops	Depth: Datum
SC		731 + 1005
B SC		767 + 969
TARK		2354 - 618
TOP		2627 - 891
HEEB		2855 - 1119
TOR		2873 - 1137
DOUG SD		2902 - 1166
LANS		2924 - 1188
BKC		3142 - 1406
RTD		3191 - 1455

8 5/8 " ^{1137J} 357-8 1/2 " 3059 ~ 150
DST (1) 3102-20 (LKC) / 45-45-45-45, 30' WM, SIP 414-312#,
FP 39-46 / 54-62#
MCT - CO, PF (DOUG) 2900-07, FRAC'D (AMT NA), SWB DWN &
REC 9 BFPH, 90% OIL, POP, P 35 80 & 30 BWPD, 9/15/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS