

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22947-00-00
Spot: E2NE Sec/Twnshp/Rge: 27-34S-15W
1320 feet from N Section Line, 660 feet from E Section Line
Lease Name: DAVIS RANCH Well #: 2-27 900
County: BARBER Total Vertical Depth: 4838 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	60		

8/19/06 KCC PGT
Per RB Dms

\$ 35.00

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 07/19/2006 6:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2006 7:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

LOST CIRCULATION AT 868'. DRY DRILLED TO 900'. STARTED OUT OF HOLE WITH DRILL PIPE & DRILLING RIG STARTED GOING DOWN AND NEARLY WENT OVER. SKIDDED RIG & DRILLED REPLACEMENT HOLE. AFTER MOVING DRILLING RIG OFF HOLE CMT WAS PUMPED DOWN RAT & MOUSE HOLE, COMMUNICATING WITH LOST HOLE. RUN BIT, DRILL COLLARS & TUBING & CLEANED WELL OUT TO 290'. PUMPED DOWN 2 3/8" TUBING WITH A TOTAL OF 235 SX CMT. HAD 3% CC IN FIRST 100 SX. HAD GOOD RETURNS THROUGH OUT. CMT CIRCULATED. QUIT PUMPING. START OUT OF HOLE WITH TUBING & DRILL COLLARS & BIT. HOLE WENT ON VACUUM. LAID DOWN PIPE. CMT DOWN APPROXIMATELY 20-25' INSIDE 20" CONDUCTOR PIPE. TOPPED OUT 20" PIPE AND CELLAR WITH 50-55 SX CMT. 7/20/06: TAGGED TOP OF CMT AT 13'. TOPPED OFF.

INVOICED
DATE 8-10-06
NO. 2007060353

RECEIVED
AUG 09 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JUL 26 2006
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)

Form [Signature]

PGT