

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20645-00-00  
Spot: SW Sec/Twnshp/Rge: 36-29S-33W  
1250 feet from S Section Line, 4030 feet from E Section Line  
Lease Name: H MCCOY Well #: 1-2  
County: HASKELL Total Vertical Depth: 2760 feet

Operator License No.: 32787  
Op Name: KANSAS NATURAL GAS OPERATING, I  
Address: PO BOX 818 1200 MAIN STREET  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2610		WITH 2 SX CMT
PROD	5.5	2748	0	WITH 580 SX CMT
SURF	8.625	600		WITH 280 SX CMT

\$ 89.70

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2006 4:00 PM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (785) 625-7353

Proposed Plugging Method: CIBP @ 2610' WITH 4 SX CMT. PLUG AT 1800' WITH 25 SX CMT. PLUG FROM 900'-0' WITH 100 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2006 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 2610' WITH 2 SX CMT. 1ST PLUG AT 1800' WITH 25 SX CMT. 2ND PLUG AT 900'-0' WITH 100 SX CMT. PUMP 2 SX CMT DOWN ANNULUS. PRESSURED TO 200 PSIG & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2738	2744		
2708	2716		
2683	2693		
2664	2672		

INVOICED  
DATE 8-10-06  
20070160357


RECEIVED  
AUG 09 2006

Remarks: USED CLASS C CEMENT BY HALLIBURTON.

KCC WICHITA

Plugged through: CSG

District: 01



Signed Jim Holland PART # \_\_\_\_\_  
(TECHNICIAN)

Form CP-2/3

PKT